

Interiors by DeX

No 131/9, MOTI Towers, 1st Floor, Rajiv Gandhi Salai, Perungudi
Chennai , Tamil Nadu, 600096
Tel: +91 87788 04499
info@interiorsbydex.com
GSTIN: 33AAXFV4242L1ZK

QUOTATION

Date: 05 Feb 2026
Quote #: QB-7D581E06

CLIENT DETAILS

Mr. Suresh pathipatti
Residential Project

CATEGORY

DeX - Xpress

Living room					
Dry / Inexposed					
Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of Wall Panel with HDF Panel , Smooth finish laminate	8 × 6 ft	48.00	1	₹1,222.00	₹58,656.00
Supply and installation of Single Raftaar Partition with 75 mm thick MR Grade Plywood and Smooth finish laminate	7 × 9 ft	63.00	1	₹1,972.00	₹1,24,236.00
Supply and installation of Base storage unit with MR Grade Plywood Carcass, HDF	8 × 1.25 ft	10.00	1	₹2,443.00	₹24,430.00
Room Subtotal:					₹4,92,878.50

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs					
Supply and installation of open storage units with SF laminate on the inner surfaces, using MR grade plywood for the carcass	1.5 × 7 ft	10.50	1	₹2,067.00	₹21,703.50
Supply and installation of black or Silver Colour Aluminium profile shutter with Tinted / Clear glass, and soft close hinges	1.5 × 7 ft	10.50	1	₹1,920.00	₹20,160.00
Supply and installation of Promise wallpaper, including complete wall surface preparation comprising touch-up putty application to rectify minor undulations	0 × 0 ft	0.00	100	₹130.00	₹13,000.00
Room Subtotal:					₹4,92,878.50

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
and imperfections, followed by one coat of oil-based primer to ensure proper adhesion. The scope includes precise cutting, alignment, joint finishing, and smooth pasting of wallpaper to achieve a neat, durable, and premium finish. - Measurement shall be calculated on a roll-wise basis. One roll shall be considered equivalent to 50 sq.ft.					
Supply and installation of gypsum false ceiling including Gyproc boards and JSW steel framework	0 × 0 ft	0.00	455	₹76.00	₹34,580.00
Providing and executing ceiling electrical works,	0 × 0 ft	0.00	455	₹71.00	₹32,305.00
Room Subtotal:					₹4,92,878.50

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
including conduit laying, wire pulling, termination, and completion					
Supply and application of Tractor emulsion paint on Gypsum false ceiling including 2 coats of putty, 1 coat of primer, and 2 coats of emulsion, complete as per site requirements	0 × 0 ft	0.00	455	₹26.00	₹11,830.00
Supply and installation of HETTICH telescopic soft-close drawer channels with complete drawer ply supports (front, back, base, and sides), including proper alignment and smooth operation.	0 × 0 ft	0.00	4	₹5,163.00	₹20,652.00
Provision of 17mm	1 × 1 ft	1.00	45	₹566.00	₹25,470.00
Room Subtotal:					₹4,92,878.50

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Concealed Profile Light with complete fixture set (Silver Colour aluminium profile, single-color LED strip, and acrylic cove cover), including wiring connection and secure mounting for a ready-to-use finish.					
Provision of Cove Light with complete fixture set (single-color LED strip, and acrylic cove cover), including wiring connection and secure mounting for a ready-to-use finish.	1 × 1 ft	1.00	160	₹460.00	₹73,600.00
Provision of 12W Single-Color LED Trance Round Downlights with fixture included, Wiring Connection,	0 × 0 ft	0.00	18	₹1,792.00	₹32,256.00
Room Subtotal:					₹4,92,878.50

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
and secure ceiling mounting for a complete ready-to-use fitting.					
Room Subtotal:					₹4,92,878.50

Dining Area

Dry / Inexposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of open storage units with SF laminate on the inner surfaces, using MR grade plywood for the carcass	4 × 3 ft	12.00	1	₹2,067.00	₹24,804.00
Supply and installation of black or Silver Colour Aluminium profile shutter with Tinted / Clear glass, and soft close hinges	4 × 2 ft	8.00	1	₹1,920.00	₹15,360.00
Supply and installation of designer aluminium profile with integrated mirror finish,	0 × 0 ft	0.00	6	₹693.00	₹4,158.00
Room Subtotal:					₹44,322.00

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
including precise fixing and a clean, seamless installation. Available aluminium finishes: Rose Gold, Black, and Silver.					
Room Subtotal:					₹44,322.00

Kitchen

Wet / Exposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and Installation of Hettich - Cargo IQ 200 (Bottle Pull out - 2 tier) Quadra Channel Size : Width -200 mm	0 × 0 ft	0.00	1	₹13,971.00	₹13,971.00
Supply and installation of Wall storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Glossy finish laminate	5 × 2 ft	10.00	1	₹2,819.00	₹28,190.00
Room Subtotal:					₹3,09,751.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
and Soft Close hinges with Finger Groove					
Supply and installation of open storage units with SF laminate on the inner surfaces, using BWP Grade Plywood for the carcass	3 × 2 ft	6.00	1	₹2,349.00	₹14,094.00
Supply and installation of black or Silver Colour Aluminium profile shutter with Tinted / Clear glass, and soft close hinges	3 × 2 ft	6.00	1	₹1,920.00	₹11,520.00
Supply and installation of Tall storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Glossy finish laminate and Soft	7 × 2 ft	14.00	1	₹2,819.00	₹39,466.00
Room Subtotal:					₹3,09,751.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Close hinges with Finger Groove					
Supply and installation of open storage units with SF laminate on the inner surfaces, using BWP Grade Plywood for the carcass	2 × 4 ft	8.00	1	₹2,349.00	₹18,792.00
Supply and installation of Tall storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Glossy finish laminate and Soft Close hinges with Finger Groove	1.5 × 7 ft	10.50	1	₹2,819.00	₹29,599.50
Supply and Installation of Hettich - OrgaTray 520 Trimmable (Fixed Partition Cutlery) Size	0 × 0 ft	0.00	1	₹1,463.00	₹1,463.00
Room Subtotal:					₹3,09,751.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
: "Width - 600mm Depth - 520mm"					
Supply and Installation of Hettich - InnoTech- 470 mm (30 Kg) Full Extn. Silent tandem - Silver Ht - 70 mm Depth - 470 mm	0 × 0 ft	0.00	2	₹5,434.00	₹10,868.00
Supply and Installation of Hettich - InnoTech- 470 mm (30 Kg) Full Extn. Silent tandem - Pot & pan drawer with railing, height 176 mm - Silver	0 × 0 ft	0.00	1	₹6,960.00	₹6,960.00
Supply and installation of EBCO Roll Top Pro – Vertical (with Overlay Rails & Cover Profile). -	0 × 0 ft	0.00	1	₹18,675.00	₹18,675.00
Room Subtotal:					₹3,09,751.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Black Colour - 600mm					
Supply and installation of Base storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Glossy finish laminate and soft close hinges with basic handles or knobs	15.5 × 2.75 ft	42.63	1	₹2,725.00	₹1,16,153.125
Room Subtotal:					₹3,09,751.625

Kitchen

Dry / Inexposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of Loft Frame and Shutter unit with MR Grade Plywood Frame, HDF Shutter, Smooth finish laminate and Soft Close hinges with Finger Groove	22 × 2 ft	44.00	1	₹1,457.00	₹64,108.00
Room Subtotal:					₹64,108.00

Master Bedroom

Dry / Inexposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of 25mm Thick Ledge MR Grade Plywood and Smooth finish laminate	2.5 × 1.75 ft	4.38	1	₹1,269.00	₹5,551.875
Supply and installation of Drawer Storage with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate with basic handles or knobs	2.5 × 2.5 ft	6.25	1	₹2,443.00	₹15,268.75
Supply and installation of HETTICH Quadro soft-close drawer channels with complete drawer ply supports (front, back, base, and sides), including proper alignment	0 × 0 ft	0.00	4	₹6,638.00	₹26,552.00
Room Subtotal:					₹3,18,633.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
and smooth operation.					
Supply and installation of Wardrobe unit with MR Grade Plywood Carcass, HDF Shutter, Designer finish laminate and soft close hinges with basic handles or knobs	6 × 7 ft	42.00	1	₹2,631.00	₹1,10,502.00
Supply and installation of Loft Frame and Shutter unit with MR Grade Plywood Frame, HDF Shutter, Smooth finish laminate and Soft Close hinges with basic handles or knobs	6 × 2 ft	12.00	1	₹1,269.00	₹15,228.00
Supply and installation of premium-quality charcoal panels complete with	5 × 7 ft	35.00	1	₹1,500.00	₹52,500.00
Room Subtotal:					₹3,18,633.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
back panels supports .					
Supply and Installation of EBCO - Foldable Bracket - wooden ledge cost excluded Ledge Depth - 600mm	0 × 0 ft	0.00	1	₹1,447.00	₹1,447.00
Supply and installation of LED mirror, inclusive of mirror glass, integrated LED lighting with driver, and touch sensor, complete with proper fixing and a neat finish.	0 × 0 ft	0.00	6	₹1,273.00	₹7,638.00
Supply and installation of Promise wallpaper, including complete wall surface preparation comprising touch-up putty application to rectify minor undulations and	0 × 0 ft	0.00	100	₹130.00	₹13,000.00
Room Subtotal:					₹3,18,633.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
imperfections, followed by one coat of oil-based primer to ensure proper adhesion. The scope includes precise cutting, alignment, joint finishing, and smooth pasting of wallpaper to achieve a neat, durable, and premium finish. - Measurement shall be calculated on a roll-wise basis. One roll shall be considered equivalent to 50 sq.ft.					
Supply and installation of gypsum false ceiling including Gyproc boards and JSW steel framework	0 × 0 ft	0.00	180	₹76.00	₹13,680.00
Supply and application of Tractor	0 × 0 ft	0.00	180	₹26.00	₹4,680.00
Room Subtotal:					₹3,18,633.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
emulsion paint on Gypsum false ceiling including 2 coats of putty, 1 coat of primer, and 2 coats of emulsion, complete as per site requirements					
Providing and executing ceiling electrical works, including conduit laying, wire pulling, termination, and completion	0 × 0 ft	0.00	180	₹71.00	₹12,780.00
Provision of 12W Single-Color LED Trance Round Downlights with fixture included, Wiring Connection, and secure ceiling mounting for a complete ready-to-use fitting.	0 × 0 ft	0.00	8	₹1,792.00	₹14,336.00
Room Subtotal:					₹3,18,633.625

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Provision of 17mm Concealed Profile Light with complete fixture set (Silver Colour aluminium profile, single-color LED strip, and acrylic cove cover), including wiring connection and secure mounting for a ready-to-use finish.	0 × 0 ft	0.00	45	₹566.00	₹25,470.00
Room Subtotal:					₹3,18,633.625

Master Bedroom Bathrom

Wet / Exposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of designer aluminium profile with integrated mirror finish, including precise fixing and a clean, seamless installation. Available aluminium	0 × 0 ft	0.00	4	₹693.00	₹2,772.00
Room Subtotal:					₹11,980.50

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
finishes: Rose Gold, Black, and Silver.					
Supply and installation of Base storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs	2 × 1.75 ft	3.50	1	₹2,631.00	₹9,208.50
Room Subtotal:					₹11,980.50

Dining - Vanity

Wet / Exposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of Base storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs	4 × 3 ft	12.00	1	₹2,631.00	₹31,572.00
Room Subtotal:					₹31,572.00

Utility

Wet / Exposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of Wall storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Glossy finish laminate and Soft Close hinges with Finger Groove	3 × 2 ft	6.00	1	₹2,819.00	₹16,914.00
Supply and installation of Tall storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Glossy finish laminate and Soft Close hinges with Finger Groove	1.5 × 6 ft	9.00	1	₹2,819.00	₹25,371.00
Supply and installation of Base storage unit with BWP Grade Plywood Carcass, HDHMR Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs	2.5 × 3 ft	7.50	1	₹2,631.00	₹19,732.50
Room Subtotal:					₹62,017.50

Kids Bedroom

Dry / Inexposed

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Supply and installation of gypsum false ceiling including Gyproc boards and JSW steel framework	0 × 0 ft	0.00	160	₹76.00	₹12,160.00
Providing and executing ceiling electrical works, including conduit laying, wire pulling, termination, and completion	0 × 0 ft	0.00	160	₹71.00	₹11,360.00
Supply and application of Tractor emulsion paint on Gypsum false ceiling including 2 coats of putty, 1 coat of primer, and 2 coats of emulsion, complete as per site requirements	0 × 0 ft	0.00	160	₹26.00	₹4,160.00
Supply and installation of Wardrobe unit with MR Grade Plywood	5 × 7 ft	35.00	1	₹2,725.00	₹95,375.00
Room Subtotal:					₹2,15,058.00

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
Carcass, HDF Shutter, Smooth finish with Mix laminate and Soft Close hinges with Basic Handels					
Supply and installation of Loft Frame and Shutter unit with MR Grade Plywood Frame, HDF Shutter, Smooth finish laminate and Soft Close hinges with basic handles or knobs	5 × 2 ft	10.00	1	₹1,269.00	₹12,690.00
Supply and installation of Wall storage unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate and Soft Close hinges with Finger Groove	5 × 2 ft	10.00	1	₹2,537.00	₹25,370.00
Supply and installation of 36mm Thick Ledge MR Grade Plywood	5 × 2 ft	10.00	1	₹1,269.00	₹12,690.00
Room Subtotal:					₹2,15,058.00

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
and Smooth finish laminate					
Supply and Installation of EBCO - Foldable Bracket - wooden ledge cost excluded Ledge Depth - 600mm	0 × 0 ft	0.00	1	₹1,447.00	₹1,447.00
Provision of 12W Single-Color LED Trance Round Downlights with fixture included, Wiring Connection, and secure ceiling mounting for a complete ready-to-use fitting.	0 × 0 ft	0.00	8	₹1,792.00	₹14,336.00
Provision of 17mm Concealed Profile Light with complete fixture set (Silver Colour aluminium profile, single-color LED strip, and acrylic cove cover), including wiring	0 × 0 ft	0.00	45	₹566.00	₹25,470.00
Room Subtotal:					₹2,15,058.00

Description	Dimensions (ft)	Sqft	Qty	Rate	Amount
connection and secure mounting for a ready-to-use finish.					
Room Subtotal:					₹2,15,058.00

Summary

Woodworks Subtotal	₹11,12,208.038
GST on Woodworks (18%)	₹2,00,197.447
Woodworks Total	₹13,12,405.484
Services Subtotal	₹1,78,103.00
GST on Services (18%)	₹32,058.54
Services Total	₹2,10,161.54
Accessories Total (GST Inclusive)	₹3,12,973.00
GRAND TOTAL	₹18,35,540.024

Terms & Conditions

Terms & Conditions

1. Quotation & Scope

Quotations are valid for 28 days unless stated otherwise.

Project scope is strictly limited to items explicitly listed in the final approved BOQ, including approved variations.

Any item not mentioned in the BOQ is deemed excluded.

2. Pricing, Changes & Approvals

Prices are based on the scope, measurements, and selections available at the time of quotation.

Any quotation issued before site documentation and design sign-off is indicative and subject to revision.

Only the Final Approved Quotation issued during

Payment Details

Total GST: ₹2,32,255.987

Generated by Interiors by DeX

design sign-off and scope freeze is commercially binding.

Any change, rework, or additional work will be treated as a variation, priced separately.

Variations will be executed only after written approval via official email.

Verbal, phone, or WhatsApp approvals are not valid for scope, cost, timelines, or variations.

3. Inclusions & Exclusions

DEX will execute only the scope mentioned in the BOQ.

Loose furniture, décor, appliances, civil/electrical/plumbing/AC works, and third-party or client-supplied items are excluded unless explicitly listed.

Products supplied by other vendors will not be installed or integrated by DEX unless stated in the BOQ.

4. Design Services

Services are delivered under an integrated design-to-execution model and are not offered as standalone design or file-licensing services.

Design revisions are subject to agreed scope and available design credits.

No editable or transferable design files are shared.

5. Token & Refunds

The token amount reserves dedicated project resources and initiates internal design, planning, and site documentation activities.

Refunds are applicable only if requested within 48 hours and before design/site documentation begins.

Once design or site work starts, the token becomes non-refundable.

6. Indicative Phase Timelines (Subject to Scope & Approvals)

Design Phase: 15–45 days

Design Validation & Sign-off: 7–14 days

Production / Execution: 35–90 days or more, depending on scope and material lead times

The above durations are indicative and may vary based on project complexity, scope changes, site conditions, material availability, and client responsiveness.

Timelines are indicative and depend on scope, site readiness, client approvals, and timely payments.

Delays in approvals, site readiness, or payments may result in timeline shifts or temporary project pause, without liability on DEX.

8. Payments

Payments must be made only to DEX's official bank account or authorized payment links. DEX is not responsible for payments made to unauthorized persons or accounts.

9. Warranty

Warranty is category-based as per DEX Warranty Card and applicable policy. Warranty exclusions include misuse, neglect, third-party intervention, and conditions outside DEX scope.

10. Intellectual Property

All designs, drawings, BOQs, and documentation remain the intellectual property of DEX. Reuse or sharing with third parties is not permitted without written consent.

11. Offers & Discounts

Discounts and offers, if any, are time-bound and governed by specific terms communicated via official email. No verbal or retrospective discount claims shall be entertained.

12. Document Hierarchy

In case of conflict, the following order applies:
Final Approved Quotation / Design Sign-off
Email-approved variations
Onboarding quotation
DEX General Policies

*Approval of this quotation confirms legal capacity to contract and acceptance of DEX policies in our website