

No	Description	Length (Ft)	Height (Ft)	Qty (sqft)	Length (mm)	Height (mm)	Unit	Rate	Quantity	Amount
Modular Work										
Shoe Rack										
	Supply and installation of Base storage unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs	2	5	10.0	600	1500	mm	2054	1	20540
Living Room										
	Supply and installation of Drawer Storage with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate with basic handles or knobs	6	1.5	9.0	1800	450	mm	2054	1	18486
	Supply and installation of black or Silver Colour Aluminium profile shutter with Tinted / Clear glass, and soft close hinges	1.5	1.5	2.3	450	450	mm	1666	1	3749
	Supply and installation of Wall Panel with HDF Panel, Smooth finish laminate	6	4	24.0	1800	1200	mm	986	1	23664
	Supply and installation of Wall Panel with HDF Panel, Designer finish laminate	6	2	12.0	1800	600	mm	1150	1	13800
Cookery										
	Supply and installation of Base storage unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate and Soft Close hinges with Finger Groove	4	1.5	6.0	1200	450	mm	2136	1	12816
	Supply and installation of Wall storage unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate and Soft Close hinges with Finger Groove	2.5	1.5	3.8	750	450	mm	2136	1	8010
	Supply and installation of 25mm Thick Ledge MR Grade Plywood and Smooth finish laminate	1	1.5	1.5	300	450	mm	1027	2	
Pool unit										
	Supply and installation of Tall storage unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs	3	7	21.0	900	2100	mm	2054	1	43134
	Providing and executing Designer CNC groove detailing on panels, finished with premium Duco paint applied to the grooved areas only.	3	4	12.0	900	1200	mm	904	1	10848
Kitchen										
	Supply and installation of Base storage unit with BWP Grade Plywood Carcass, HDF Shutter, Glossy finish laminate and soft close hinges with basic handles or knobs	16.5	2.75	45.4	4950	825	mm	2301	1	104408
	Supply and installation of Wall storage unit with BWP Grade Plywood Carcass, HDF Shutter, Glossy finish laminate and soft close hinges with basic handles or knobs	9	2.25	20.3	2700	675	mm	2301	1	46595
	Supply and installation of open storage units with SF laminate on the inner surfaces, using BWP Grade Plywood for the carcass	2.75	2.25	6.2	825	675	mm	1972	1	12202
	Supply and installation of black or Silver Colour Aluminium profile shutter with Tinted / Clear glass, and soft close hinges	2.75	2.25	6.2	825	675	mm	1666	1	10308
	Supply and installation of Left Frame and Shutter unit with BWP Grade Plywood Frame, HDF Shutter, Glossy finish laminate and Soft Close hinges with basic handles or knobs	12	2.5	30.0	3600	750	mm	1274	1	38220
	Supply and installation of Base Panel with BWP Grade Plywood, Glossy finish laminate	12	2.5	30.0	3600	750	mm	1232	1	36960
	Supply and installation of Tall storage unit with BWP Grade Plywood Carcass, HDF Shutter, Glossy finish laminate and soft close hinges with basic handles or knobs	2	7	14.0	600	2100	mm	2301	1	32214
	Supply and installation of 25mm Thick Ledge BWP Grade Plywood and Glossy finish laminate	1.75	1	1.8	525	300	mm	1274	3	6689
Master Bedroom										
	Supply and installation of Wardrobe unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish laminate and soft close hinges with basic handles or knobs	5	7	35.0	1500	2100	mm	2054	1	71890
	Supply and installation of premium-quality Metal Inlays on top of the panels	16	1	16.0	4800	300	mm	657	1	10512
Master Bedroom										
	Supply and installation of Wardrobe unit with MR Grade Plywood Carcass, HDF Shutter, Smooth finish with Mix laminate and Soft Close hinges with Basic Handles	5	7	35.0	1500	2100	mm	2301	1	80535
	Supply and installation of premium-quality Metal Inlays on top of the panels	16	1	16.0	4800	300	mm	657	1	10512
TRANSPORTATION,LOADING & UNLOADING										10000
SUB TOTAL										616091
Discount 15%										533678
GST 18%										96062
GRAND TOTAL										629740

Quotation - Accessories:										
SNo	Description	Packing	Nos		Images	Packing	Nos	Unit Price	Price	
1	Supply and Installation of Ebco (Livsmart) - PVC Cutlery tray - AT finish ; Size: Width - 450mm Depth - 490mm	Nos	1			Nos	1	₹1,051	₹1,051	
2	Supply and installation of Ebco (Livsmart) Pro-Motion Drawer System – Model 90 (S3-AT), PMDS1-50-S3 specification." ; Size: 90x500mm, 50Kg	Set	2			Set	2	₹3,242	₹6,483	
3	Supply and installation of Ebco (Livsmart) Pro-Motion Drawer System – System 172 (S3-AT), Model PMDS3-50-S3. ; Size: 172x500mm, 50Kg	Set	1			Set	1	₹3,926	₹3,926	
4	Supply and installation of EBCO Bottle Pullout 2 – Soft Close – Glass (Full set with 2-tier solid base basket, soft close slides, and mounting kit) - 150mm ; Size: 105x470x555 (for 150 mm cabinet)	Nos	1			Nos	1	₹8,788	₹8,788	
5	Supply and Installation of Ebco (Livsmart) - 4" PVC Wicker basket with wooden frame and slide - 450 mm ; Size: 412*496*100 mm	Nos	1			Nos	1	₹5,272	₹5,272	
6	Supply and Installation of Hafele Slido F-U18 50-Hardware set for 2 door Concealed Track ; Size: Wardrobe - Minimum length 7 feet	Set	1			Set	1	₹13,883	₹13,883	
7	Supply and installation of EBCO telescopic soft-close drawer channels with complete drawer ply supports (front, back, base, and sides), including proper alignment and smooth operation.	Nos	8			Nos	8	₹20,294	₹162,351	
TOTAL									₹201,754	
The NETT Total Accessories price is Inclusive of FIXING, GST & TRANSPORTATION										

Quotation - Civil:										
No	Description	Length	Height	Qty	Length	Height	Unit	Amount		
								Rate		Amount
	CIVIL WORK									
	Supply and installation of 2.5mm thick floor protection sheet	492	1	492		492	Sqft		16	₹7,995
	Supply and installation of gypsum false ceiling including Gyproc boards and JSW steel framework	492	1	492		492	Sqft		76	37579
	Providing and executing ceiling electrical works, including conduit laying, wire pulling, termination, and completion	492	1	492		492	Sqft		71	35055
	Supply and application of Tractor emulsion paint on Gypsum false ceiling including 2 coats of putty, 1 coat of primer, and 2 coats of emulsion, complete as per site requirements	492	1	492		492	Sqft		26	12915
	Provision of 17mm Concealed Profile Light with complete fixture set (aluminium profile, single-color LED strip, and acrylic cove cover), including wiring connection and secure mounting for a ready-to-use finish.	15	1	15		15	Rft		480	7200
	Provision of 12W Single-Color LED Trance Round Downlights with fixture included, Wiring Connection, and secure ceiling mounting for a complete ready-to-use fitting.	15	1	15		15	Nos		1519	22785
	Providing AGL Quartz – Coasta Maple finish, inclusive of material cost, loading, unloading, and transportation to site.	1	1	1		1	Nos		30929	30929
	Quartz Countertop Installation (Adhesive Fixing) – Quartz Material cost Excluded Rate includes installation of the Quartz countertop using adhesive, double-nosing edge polishing, hob cutting, and sink cutting with fixing. Sink and hob cutting charges are applicable for one sink and one hob only. Exclusions: Quartz material cost, sink cost, and all plumbing works.	17	2	34		34	Sqft		536	18224
	5*2 tile Installation on wall using Adhesive (Tile Material Cost Excluded): The rate includes installation of the wall Tile on the kitchen wall back splash	17	2	34		34	Sqft		228	7745
SUB TOTAL										180427
GST 18%										32477
GRAND TOTAL										212904
CUMULATIVE GRAND TOTAL										
Modular Work										INR
Accessories										629740
Civil Work										201754
TOTAL										212904
CUMULATIVE GRAND TOTAL										
TOTAL										1044398
PAYMENT SCHEDULE										
Project Advance - 10%										INR
Upon Design Sign Off - 50%										104440
Upon Modular Material Delivery - 35%										522199
Upon Completion (Before Handover) - 5%										365539
TOTAL										52220
TOTAL										1044398

82000
12300
69700
82246
